

Internap Japan Tokyo Data center

April, 2015
Internap Japan



■ About Internap Japan

Internap Japan has been providing high performance, low latency IP transit solutions for enterprise since 2001. Driven by our patented routing technology MIRO, and supported by a team of world class bilingual engineers 24x7, our mission is to ensure that our customers achieve the highest performance possible when using us to support their online businesses.

Company Name	Internap Japan Co.,Ltd.
Headquarters	7th Floor Kanda Kaji-cho Chitose Bldg., 3-3-12 Kanda Kaji-cho, Chiyoda-ku, Tokyo 101-0045 Japan
Capital	526,000,000Yen
Shareholders	Internap Network Services Corporation 51% NTT-ME Corporation 40% Nippon Telegraph and Telephone Corporation 9%
Foundation	April 10, 2001
Contacts	+81-3-5209-2222 (Telephone) +81-3-5209-2221 (Fax)
Location of Osaka office	COSMIC Bldg. No.30., 2-2-4 Uchihiranomachi, Chuo-ku, Osaka 540-0037 Japan
Official Homepage	http://www.internap.co.jp
CEO	Masaki Okuno



Internap Japan Tokyo Data center

A key component of Internap's Information Delivery Platform

Building	
Location	Shiohama, Koto-ku, Tokyo
Total Floor Area	22,000 m ²
Stories	8 stories above grade, ,1 story below grade (5 floors of server room space)
Structure	Aseismatic (RC & Reinforced structure) Various natural hazard preventions (foundation improvement, liquefaction countermeasures, quakeproof enhancements etc.)
Purpose	Exclusively for corporate Data Center
Facilities	
Power	66kV extra-high tension power source (2 loop circuits), UPS (Redundant), Generator (N+1, Preferred refueling contracts)
A/C	CRAC (N+1, Water cooling), Cooling capacity of 750~850W/m ²
Fire Extinction	Ultra high-sensitive smoke detectors (VESDA), Temperature sensors, Inergen gas fire extinction etc.
Security	Security & monitoring (24x7), entrance administration (ID card, password, fingerprint authentication), Security cameras etc.
Server Space	
Rack space	10,800 m ² approx.
Number of racks	3,700 racks approx.
Slab height	3,800~4,200 mm
Double under floor height	500 mm
Floor loading	Raised floor 500 kg/ m ² (when using cradle 1,500/m ²)
Power capacity	Average 750~850 W/m ² , Maximum 1.5~1.7 kW/m ²
Staging room	Available (Different area from server rooms, advanced reservation is required.)



Appearance

FISC compliance

Tokyo Data center complies with FISC requirements. Many financial firms are our customers.

ISMS (ISO27001) standard compliance

Data center obtain ISMS certification for domestic and international services.



IS 87997/ISO (JIS Q) 27001

SSAE16 Type- II report recognition

Data center has recognition of internal control reports and reports on the maintenance and operation status of internal control for the physical security and facility environment administration of TDC1 and TDC2

■ Global Standard Reliability

• Reliability and Safety of International Standards

- Meeting the mission-critical needs of the financial industry

• High Quality Services

- Adopting state-of-the-art technology
- Experienced and skilled engineers
- 24 x 365 bilingual support

• One-stop and Integrated Service Offering

- Integration of communication and data center services
- Full suite of data center services
- Direct connection Internap's Internet backbone

• Internal Control

- “SSAE16 Type II report” recognition

• Information Security

- ISMS “ISO(JIS Q) 27001” standards compliance



SSAE16
Type II Audit Complete



IS 87997 / ISO (JIS Q) 27001

■ Internap Tokyo Data center Design Philosophy

Internap Tokyo Data center was specifically designed to meet the demanding needs of the financial services industry in terms of resilience and security



Convenience

- Close physical proximity to all major Japanese exchanges
- Located in city center
- Flexibility to choose from a variety of carriers



Reliable and Secure


- Redundant 2(N+1) power
- High level of security



Regulations

- ISMS/ISO27001
- SSAE16 Type 2
- FISC

■ DC In-Building Cabling



- Carrier Neutral Facility – In addition to Internap, KVH, NTT East and KDDI deliver telecom services from this building
- Four risers are located in two separate fire protected zones on each floor. Primary and secondary cables are installed through different risers on each floor
- Two MDF rooms are located in two different fire separated zones
- Each Main Fiber is connected to MDF rooms and fiber is brought into the building through four access points



■ Purpose-Build DC with Redundancy

Power

- Closed loop for diverse power feeds (active-active)
- Variable power supply can be offered (N, N+1, 2N, 2(N+1), NN)
- UPS; double string batteries, 10 minutes at full load
- Gas turbine generators in an N+1 configuration

Cooling

- Server rooms are equipped with N+1 Computer Room Air Conditioning (CRAC) units, each with dual refrigeration compressors for accurate cooling capacity over the entire raised floor. The total cooling capacity may exceed 850W/m²
- Temperature setting is $22 \pm 2^{\circ}\text{C}$, Humidity setting is $45 \pm 5\%$
- The building is cooled with fully looped condenser water cooling systems. The cooling towers are mounted on the roof
- All facilities are designed with N+1 redundancy

Fuel



- Minimum of 48 hours without refueling. Another 24 hours is possible by guaranteed refueling within 48 hours. (continuously refueling)
- Preferred refueling contracts with suppliers

■ Security



Integrated security monitoring system with multi-layered authentication, verification and surveillance to limit access to authorized personnel

- Data retrieved from biometric and password systems is integrated with the video surveillance system
- Security personnel on-site 24x7x365, continuously monitoring security systems
- 9-level security system – additional security options possible (8 check points on 7th floor)



■ Certifications



Compliance with recognized international standards is a central part of our operational and security procedures.

Data centers conform to the following major regulations:

- **ISMS**

Data center owner operates in accordance to the Information Security Management System (referred to as "ISMS"), with having attained ISO 27001 security standard compliance (ISO/IEC 27001:2005/JIS Q 27001:2006).

- **SSAE16**


Data center has received the Statement on Standards for Attestation Engagements No.16 (SSAE16 Type II), developed by the American Institute of Certified Public Accountants (AICPA), for its physical security and environmental control of co-location and/or wholesale services delivered .

- **FISC**

Data centers is compliant with Japan FISC (Financial Industry Information Systems) guidelines.

- **Appendix**


■ Anti-Seismic Structure



- **Soil improvement, anti-liquefaction**
As an anti-liquefaction measure, 130 piles with a diameter of 2.5 meters were drilled 13 meters deep into soil layers. According to this anti-liquefaction treatment, the seismic resistant performance of the building has been significantly upgraded to withstand the most powerful earthquakes.
- **Structural reinforcement**
Unbonded bracing was installed to further improve the seismic performance of the moment resisting frame structure and to increase the seismic load capacity.
To support the mission-critical facility's heavy infrastructure, supportive columns, beams, and slab reinforcement were carried out on the roof, terraces and lower parts of the building.

Power Facilities

- Receiving systems**
 Two 66kV Closed Loop Receiving Systems from TEPCO.
- Average power capacity**
 2F, 3F and 7F
 Average power capacity: 750w/m²
 Max power: 1,500w/m²
 4F and 5F
 Average power capacity: 850w/m²
 Max power: 1,700w/m²
- Scalability**
 By expanding PDU and RPP board, it is possible to increase power capacity by 25%.
- UPS**
 10 minutes under full load
- Power generator**
 Power supplied under full load for minimum 72 hours.
 For minimum 48 hours without refueling.
 Another 24 hours is possible by guaranteed refueling within 48 hours.
 (continuously more refueling)



■ Air Conditioning System

- **Air cooling system**

The building is cooled with fully looped condenser water cooling systems. The cooling towers are mounted on the roof.

- **Water leak measure**


Water leak sensors are installed on pipes and CRACs, and each CRAC has watertight edges and drains installed at the front.

- **Redundancy**

All facilities are designed with N+1 redundancy. The fully looped condenser water piping system on the roof provides dual path water feeds to the computer room air-conditioners.

- **Scalability**

Vertical condenser water distribution allows for fast and easy installation of additional CRAC units for additional cooling needs and rapid build-out of raised floor areas.



■ Generator Fuel System

Fuel type

- Special Grade A Oil


Maintenance schedule

- Monthly start-up test (no load)
- Annual load test
- Weekly visual inspection
- Annual maintenance

Continuous fuel supply monitoring system


- When the generators start-up at an unscheduled time, a signal is automatically sent to the fuel supplier to replenish the fuel tanks

Fuel Supply Network



■ Fire Prevention

To detect a fire at a very early stage, ultra high-sensitive smoke detectors (VESDA), smoke detectors and temperature sensors are used to activate the fire extinguishing facilities in 3 phases.




	Phase 1	Phase 2	Phase 3
Sensor	VESDA (Very Early Smoke Detection Apparatus)	Smoke detectors	Temperature sensor
Suppression method	Portable CO₂ based fire extinguisher	INERGEN 541 (N ₂ , Ar, CO ₂)	Pre-action sprinkler

■ Server Room

Server Room

Internap Tokyo Data Center 1 offers various colocation menus from 1 rack unit to the entire server room space. Customers can operate their system within the same space without needing to divide it.



※The above server room and staging room are the images us only

Multipurpose Staging Room

Multipurpose staging rooms are available for Data Center Users. The staging rooms where customers unpack and set up their devices are provided with security measurements. The staging rooms always have tables, chairs, internet connectivity and telephones.

* Advanced reservations are required to use the staging rooms

Staging Room	Floor	Area
Room 504	5F	22 m ²
Room 503	5F	18 m ²
Room 502	5F	14 m ²
Room 501	5F	11 m ²
Room 3F	3F	32 m ²



■ Floor Design

- **Floor**

Room height 3,300mm (2F/3F/4F/7F)
3,700mm (5F)

The room on 5F is 400mm higher than that of the other floors. Therefore, the height and cooling efficiency is superior and more equipment can be housed on 5F than on other floors.

Floor height 500mm

- **Free Access (double floor)**

Anti-seismic double floor with 4 points fixed to prevent panels from falling out during an earthquake.

Withstand load

design 500kg/m²


Horizontal load

bearing 1.0G (jointed)

Vertical load

bearing 1.0G

Whisker countermeasure implemented (galvanized) (7F)



■ Standard Rack for 4F, 5F, 7F

Standard 19 inch rack of EIA standards is available to use as 1 full rack or half rack unit. In order to meet customer's requests for 24 x 365 nonstop use, power supply systems to the racks and UPS provided for each power supply are available. Standard racks on 7F are part of 6 shot fan models that have a high rate of exhaust heat, depending on the location.

Specifications	19 inch full rack		19inch half rack
Size	19 inch rack		
External size W×D×H (unit: mm)	4F: 600×1000×2000	4F/7F: 700×1000×2000	700x1000x1000
	5F: 600×1000×2200	5F: 700×1000×2200	
Mount frame standard	EIA standard		
Effective mount unit number	4F/7F: 42U / 5F: 46U		20U
Seismic Adeqnacy	Paas the test for Kobe earthquake wave 800gal (3Axis Simultaneous Vibration 300kg load capacity)		
Power System	1 or 2 systems		
Outlet bar	100V20A	20 ports (outlet bar)	4 port OA tap (standard) Up to 6 ports (outlet bar)
	100V30A	18 ports (outlet bar)	6 ports (standard) (outlet bar)
	200V20A,30A,50A	Under floor box transfer	
Power cable	Introduced from the open/close to the free access floor		
Plug form	NEMA L6-20、L6-30 others		
Front/back panel	Punching metal		
Key	Handle key (4 digits pass code) + key rock		
Fan	Fanless ceiling		
Others	Remote hands (5 times/month)		Remote hands (3 times/month)
Rack mount load	Static load 500kg	Static load 500kg	Static load 250kg
Demarcation	Communication port/OA tap	Communication port/OA tap	Communication port/OA tap



- Remote hands is the primary maintenance work and includes lump visual check, power on/off etc. based on the customer's operation manual.
- Contact with our sales representatives regarding the delivery of customer's racks.
- Cage service to surround customer's space with a cage for security is available.

■ Standard Rack for 2F, 3F, 7F

Standard 19 inch rack of EIA standards is available to use as 1 full rack or half rack unit. In order to meet customer's requests for 24 x 365 nonstop use, power supply system to the racks and UPS provided for each power supply are available.

※Standard racks on 7F are part of 6 shot fan models that have a high rate of exhaust heat, depending on the location.

Specifications	19 inch full rack		19 inch half rack
Size	19 inch rack		
Outer size W×D×H (unit: mm)	700×1000×2000	600×900×2000	600×900×1000
Mount frame standard	EIA standard		
Effective mount unit number	41U		20U
Seismic adequacy	1.0 G @maximum capacity		
Power system	1 or 2 system (UPS power)		
Outlet bar	100V 20A,30A,30A common	17 ports (OA tap)	4 ports (standard) 、 Up to 10 ports
	200V20A,30A,50A	Under floor box transfer	
Power cable	Introduced from the open/close to the free access floor		
Plug form	NEMA L6-20、 L6-30 and others		
Front back panel	Punching metal		
Key	Handle key (4 digits pass code) + key rock		
Fan	4 shot fan on the ceiling		
Others	Remote hands (5 times/month)		Remote hands (3 times/month)
Rack mount load capacity	380kg	400kg	190kg
Demarcation	Communication port/OA tap	Communication port/OA tap	Communication port/OA tap



- Remote hands is the primary maintenance work and includes lump visual check, power on/off etc. based on the customer's operation manual.
- Contact with our sales representative about bringing customer's racks.
- Cage service to surround customer's space with the cage for security is available.